

## **Addendum-1**

**TENDER**

**FOR**

**EXCAVATION OF WATERBODIES AND CHANNEL DEEPENING WORKS AT DTA-II AT  
MAHINDRA WORLD CITY,JAIPUR**

**Tender No:** MWCJL/INFRA/DTA-II/EXCAV.WATERBODY/2018-19/T-011

**Part-IV -BOQ (attached)**

**Revised Bid Submission Date:- 12.12.2018**

**Note:-**

**All the terms and Conditions shall remain same as per earlier floated above mentioned Tender**

## Bill of Quantities Water body deepening at DTA-II Phase-I

S.No.	Description	Unit	Qty.	Rate	Amount
1	Excavation upto 1.5 mtr including disposal and levelling as per direction of Enginner -in-Charge for, including etc. including, dewatering, timbering, shoring & strutting, dressing of sides and ramming of bottoms , cost of Transportation upto lead of 2.5 Km and Filling available excavated earth (excluding rock) in Vertical Spine Road (Service Corridor filling) including levelling and filling in layers not exceeding 20cm in depth , consolidating each deposited layer by ramming & watering.	cum	8,073		
2	Excavation upto 1.5 mtr including disposal and levelling as per direction of Enginner -in-Charge for, including etc. including, dewatering, timbering, shoring & strutting, dressing of sides and ramming of bottoms , cost of Transportation upto lead of 2 Km and Filling available excavated earth (excluding rock) in Social Infra Plots including levelling and filling in layers not exceeding 20cm in depth , consolidating each deposited layer by ramming & watering.	cum	67,927		-
3	Excavation upto 1.5 mtr including disposal and levelling as per direction of Enginner -in-Charge for, including etc. including, dewatering, timbering, shoring & strutting, dressing of sides and ramming of bottoms , cost of Transportation upto lead of 1.5 Km and Filling available excavated earth (excluding rock) in Social Infra Plots including levelling and filling in layers not exceeding 20cm in depth , consolidating each deposited layer by ramming & watering.	cum	Rate Only		
Total					
GST @ 18%					
Total					
1	Rate shall is inclusive of cess,all charges ,labour charges except GST, which is payable as mentioned above.				
2	Time is essence of the Contract. Work to be completed within 25 days.				
3	Any extra Items /increase in qtys. other than BOQ shall be pre-intimated before execution. Such Items shall be recorded in Site Instruction book and same shall be paid as per approval by Engineer-in Charge based on proper rate analysis (in case of extra items) by Contracts Deptt.				
4	Requirement of free issue material to be informed in advance.Reconcillition to be done on every R.A.Bills for the free issue material and physical stock to be given for the free issue material every month.				